



Proposal Schedule of Items

Proposal ID: 20180612010 Project(s): 2060-10-70

Federal ID(s): WISC 2018319

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0120 Clearing	832.000 ID		
0004	201.0220 Grubbing	832.000 ID		
0006	204.0100 Removing Pavement	49,400.000 SY		
0008	204.0115 Removing Asphaltic Surface Butt Joints	600.000 SY		
0010	204.0150 Removing Curb & Gutter	90.000 LF		
0012	204.0155 Removing Concrete Sidewalk	3,500.000 SY		
0014	204.0195 Removing Concrete Bases	11.000 EACH		
0016	204.0250 Abandoning Manholes	9.000 EACH		
0018	204.0260 Abandoning Inlets	48.000 EACH		
0020	204.9105.S Removing (item description) 01. Loop Detector Wire & Lead-In Cable STH 38 & Grange Avenue	LS	LUMP SUM	
0022	205.0100 Excavation Common	41,917.000 CY		
0024	205.0501.S Excavation, Hauling, and Disposal of Petroleum Contaminated Soil	4,096.000 TON		
0026	213.0100 Finishing Roadway (project) 01. 2060-10-70	1.000 EACH		
0028	305.0110 Base Aggregate Dense 3/4-Inch	500.000 TON		
0030	305.0120 Base Aggregate Dense 1 1/4-Inch	63,605.000 TON		



Proposal Schedule of Items

Proposal ID: 20180612010 Project(s): 2060-10-70

Federal ID(s): WISC 2018319

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	320.0125 Concrete Base 6-Inch	510.000 SY		
0034	405.0200 Coloring Concrete Custom	208.000 CY		
0036	415.0080 Concrete Pavement 8-Inch	49,100.000 SY		
0038	416.0180 Concrete Driveway 8-Inch	1,340.000 SY		
0040	416.0610 Drilled Tie Bars	41.000 EACH		
0042	440.4410 Incentive IRI Ride	10,500.000 DOL	1.00000	10,500.00
0044	455.0605 Tack Coat	50.000 GAL		
0046	465.0105 Asphaltic Surface	200.000 TON		
0048	601.0150 Concrete Curb Integral Type D	10,200.000 LF		
0050	601.0319 Concrete Curb & Gutter 19-Inch	163.000 LF		
0052	601.0331 Concrete Curb & Gutter 31-Inch	9,970.000 LF		
0054	601.0600 Concrete Curb Pedestrian	60.000 LF		
0056	602.0410 Concrete Sidewalk 5-Inch	49,050.000 SF		
0058	602.0515 Curb Ramp Detectable Warning Field Natural Patina	370.000 SF		
0060	602.0615 Curb Ramp Detectable Warning Field Radial Natural Patina	110.000 SF		
0062	611.2004 Manholes 4-FT Diameter	27.000 EACH		



Proposal Schedule of Items

Proposal ID: 20180612010 Project(s): 2060-10-70

Federal ID(s): WISC 2018319

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0064	611.2006 Manholes 6-FT Diameter	5.000 EACH		
0066	611.3225 Inlets 2x2.5-FT	2.000 EACH		
0068	612.0106 Pipe Underdrain 6-Inch	260.000 LF		
0070	612.0208 Pipe Underdrain Unperforated 8-Inch	29.000 LF		
0072	618.0100 Maintenance And Repair of Haul Roads (project) 01. 2060-10-70	1.000 EACH		
0074	619.1000 Mobilization	1.000 EACH		
0076	620.0300 Concrete Median Sloped Nose	1,390.000 SF		
0078	621.0100 Landmark Reference Monuments	2.000 EACH		
0080	623.0200 Dust Control Surface Treatment	49,100.000 SY		
0082	624.0100 Water	213.000 MGAL		
0084	625.0100 Topsoil	8,300.000 SY		
0086	625.0105 Topsoil	640.000 CY		
0088	627.0200 Mulching	2,880.000 SY		
0090	628.7570 Rock Bags	30.000 EACH		
0092	629.0210 Fertilizer Type B	5.000 CWT		
0094	631.1000 Sod Lawn	8,300.000 SY		



Proposal Schedule of Items

Proposal ID: 20180612010 Project(s): 2060-10-70

Federal ID(s): WISC 2018319

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	632.0101 Trees (species) (size) (root) 01. FREEMAN MAPLE, 4" CAL, B&B	3.000 EACH		
0098	632.0101 Trees (species) (size) (root) 02. CLEVELAND SELECT PEAR, 4" CAL, B&B	27.000 EACH		
0100	632.0101 Trees (species) (size) (root) 03. IVORY SILK LILAC, 4" CAL, B&B	14.000 EACH		
0102	632.0101 Trees (species) (size) (root) 04. AMERICAN HORNBEAN, 4" CAL, B&B	9.000 EACH		
0104	632.0101 Trees (species) (size) (root) 05. Skyline Honey Locust, 4" CAL, B&B	12.000 EACH		
0106	632.0101 Trees (species) (size) (root) 06. Autumn Fantasy Maple, 4" CAL, B&B	8.000 EACH		
0108	632.0101 Trees (species) (size) (root) 07. Autumn Blaze Maple, 4" CAL, B&B	10.000 EACH		
0110	632.9101 Landscape Planting Surveillance and Care Cycles	10.000 EACH		
0112	634.0618 Posts Wood 4x6-Inch X 18-FT	26.000 EACH		
0114	637.2210 Signs Type II Reflective H	314.500 SF		
0116	638.2102 Moving Signs Type II	1.000 EACH		
0118	638.2602 Removing Signs Type II	9.000 EACH		
0120	638.3000 Removing Small Sign Supports	7.000 EACH		
0122	641.8100 Overhead Sign Support (structure) 01. S- 40-648	LS	LUMP SUM	



Proposal Schedule of Items

Proposal ID: 20180612010 Project(s): 2060-10-70

Federal ID(s): WISC 2018319

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0124	641.8100 Overhead Sign Support (structure) 01. S-40-649	LS	LUMP SUM	_____
0126	641.8100 Overhead Sign Support (structure) 02. S-40-650	LS	LUMP SUM	_____
0128	642.5401 Field Office Type D	1.000 EACH	_____	_____
0130	643.0300 Traffic Control Drums	48,996.000 DAY	_____	_____
0132	643.0420 Traffic Control Barricades Type III	35,772.000 DAY	_____	_____
0134	643.0500 Traffic Control Flexible Tubular Marker Posts	542.000 EACH	_____	_____
0136	643.0600 Traffic Control Flexible Tubular Marker Bases	542.000 EACH	_____	_____
0138	643.0900 Traffic Control Signs	21,070.000 DAY	_____	_____
0140	643.5000 Traffic Control	1.000 EACH	_____	_____
0142	644.1410.S Temporary Pedestrian Surface Asphalt	17,200.000 SF	_____	_____
0144	644.1420.S Temporary Pedestrian Surface Plywood	5,680.000 SF	_____	_____
0146	644.1430.S Temporary Pedestrian Surface Plate	430.000 SF	_____	_____
0148	644.1601.S Temporary Curb Ramp	9.000 EACH	_____	_____
0150	645.0112 Geotextile Type DF Schedule B	79.000 SY	_____	_____
0152	646.1020 Marking Line Epoxy 4-Inch	5,050.000 LF	_____	_____
0154	646.3020 Marking Line Epoxy 8-Inch	2,625.000 LF	_____	_____



Proposal Schedule of Items

Proposal ID: 20180612010 Project(s): 2060-10-70

Federal ID(s): WISC 2018319

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0156	646.5020 Marking Arrow Epoxy	14.000 EACH		
0158	646.5120 Marking Word Epoxy	13.000 EACH		
0160	646.5220 Marking Symbol Epoxy	1.000 EACH		
0162	649.0150 Temporary Marking Line Removable Tape 4-Inch	66,248.000 LF		
0164	649.0550 Temporary Marking Arrow Removable Tape	16.000 EACH		
0166	649.0650 Temporary Marking Word Removable Tape	15.000 EACH		
0168	649.0850 Temporary Marking Stop Line Removable Tape 18-Inch	162.000 LF		
0170	650.4000 Construction Staking Storm Sewer	80.000 EACH		
0172	650.4500 Construction Staking Subgrade	10,500.000 LF		
0174	650.7000 Construction Staking Concrete Pavement	10,500.000 LF		
0176	650.8500 Construction Staking Electrical Installations (project) 01. 2060-10-70	LS	LUMP SUM	
0178	650.9000 Construction Staking Curb Ramps	27.000 EACH		
0180	650.9910 Construction Staking Supplemental Control (project) 01. 2060-10-70	LS	LUMP SUM	
0182	650.9920 Construction Staking Slope Stakes 01. 2060-10-70	4,630.000 LF		



Proposal Schedule of Items

Page 7 of 14

Proposal ID: 20180612010 Project(s): 2060-10-70

Federal ID(s): WISC 2018319

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0184	652.0220 Conduit Rigid Nonmetallic Schedule 40 1 1/2-Inch	55.000 LF		
0186	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	697.000 LF		
0188	652.0230 Conduit Rigid Nonmetallic Schedule 40 2 1/2-Inch	2,033.000 LF		
0190	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	5,168.000 LF		
0192	652.0330 Conduit Rigid Nonmetallic Schedule 80 2 1/2-Inch	357.000 LF		
0194	652.0335 Conduit Rigid Nonmetallic Schedule 80 3-Inch	3,499.000 LF		
0196	652.0605 Conduit Special 2-Inch	5.000 LF		
0198	652.0610 Conduit Special 2 1/2-Inch	39.000 LF		
0200	652.0615 Conduit Special 3-Inch	75.000 LF		
0202	652.0800 Conduit Loop Detector	442.000 LF		
0204	653.0154 Pull Boxes Non-Conductive 24x36-Inch	1.000 EACH		
0206	653.0900 Adjusting Pull Boxes	2.000 EACH		
0208	653.0905 Removing Pull Boxes	1.000 EACH		
0210	654.0101 Concrete Bases Type 1	17.000 EACH		
0212	654.0113 Concrete Bases Type 13	3.000 EACH		



Proposal Schedule of Items

Page 8 of 14

Proposal ID: 20180612010 Project(s): 2060-10-70

Federal ID(s): WISC 2018319

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0214	655.0305 Cable Type UF 2-12 AWG Grounded	3,187.000 LF		
0216	655.0700 Loop Detector Lead In Cable	1,410.000 LF		
0218	655.0800 Loop Detector Wire	1,768.000 LF		
0220	657.0100 Pedestal Bases	17.000 EACH		
0222	690.0150 Sawing Asphalt	1,820.000 LF		
0224	690.0250 Sawing Concrete	80.000 LF		
0226	715.0415 Incentive Strength Concrete Pavement	14,730.000 DOL	1.00000	14,730.00
0228	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,100.000 HRS	5.00000	10,500.00
0230	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	3,500.000 HRS	5.00000	17,500.00
0232	SPV.0035 Special 01. ENGINEERED SOIL	111.000 CY		
0234	SPV.0035 Special 02. BEDDING LAYER	26.000 CY		
0236	SPV.0045 Special 01. TEMPORARY CROSSWALK	225.000 DAY		
0238	SPV.0060 Special 01. INLET COVERS TYPE 57	82.000 EACH		
0240	SPV.0060 Special 02. MANHOLE COVERS TYPE 58A	62.000 EACH		
0242	SPV.0060 Special 03. INLETS TYPE 45A	50.000 EACH		
0244	SPV.0060 Special 04. INLET COVERS TYPE 55	6.000 EACH		



Proposal Schedule of Items

Proposal ID: 20180612010 Project(s): 2060-10-70

Federal ID(s): WISC 2018319

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0246	SPV.0060 Special 05. INLET SCREEN TYPE M	82.000 EACH		
0248	SPV.0060 Special 06. INLET SCREEN TYPE R	82.000 EACH		
0250	SPV.0060 Special 07. ADJUSTING WATER BOXES	80.000 EACH		
0252	SPV.0060 Special 08. 8" DIAMETER OVERFLOW STANDPIPE WITH DOME GRATE	4.000 EACH		
0254	SPV.0060 Special 09. INFORMATIONAL SIGN POSTS	2.000 EACH		
0256	SPV.0060 Special 10. 6 INCH CLEANOUT	7.000 EACH		
0258	SPV.0060 Special 11. KARL FORESTER GRASS, #1, CG	24.000 EACH		
0260	SPV.0060 Special 12. INLET FRAME AND GRATE	6.000 EACH		
0262	SPV.0060 Special 13. POLES TYPE 12	2.000 EACH		
0264	SPV.0060 Special 14. POLES TYPE 13	1.000 EACH		
0266	SPV.0060 Special 15. POLE TYPE 12 SPECIAL	3.000 EACH		
0268	SPV.0060 Special 16. MONOTUBE ARM 40'	3.000 EACH		
0270	SPV.0060 Special 17. MONOTUBE ARM 45 FOOT	1.000 EACH		
0272	SPV.0060 Special 18. MONOTUBE ARM 55 FOOT	2.000 EACH		
0274	SPV.0060 Special 19. CONCRETE BASE TYPE 10 SPECIAL	3.000 EACH		



Proposal Schedule of Items

Page 10 of 14

Proposal ID: 20180612010 Project(s): 2060-10-70

Federal ID(s): WISC 2018319

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0276	SPV.0060 Special 20. LUMINAIRE 105 WATTS LED STREET LIGHT	17.000 EACH		
0278	SPV.0060 Special 21. LUMINAIRE 141 WATTS LED STREET LIGHT	77.000 EACH		
0280	SPV.0060 Special 22. LUMINAIRE ARM ALUMINUM DOUBLE BRACKET 6'	18.000 EACH		
0282	SPV.0060 Special 23. LUMINAIRE ARM ALUMINUM DOUBLE BRACKET 8'	23.000 EACH		
0284	SPV.0060 Special 24. LUMINAIRE ARM ALUMINUM SINGLE BRACKET 8'	9.000 EACH		
0286	SPV.0060 Special 25. FIBERGLASS/POLYMER CONCRETE PULL BOXES 13"X24"X24"	33.000 EACH		
0288	SPV.0060 Special 26. FIBERGLASS/POLYMER CONCRETE PULL BOXES 17"X30"X24"	31.000 EACH		
0290	SPV.0060 Special 27. BOLT DOWN ALUMINUM POLE 14' WITH TRANSFORMER BASE	3.000 EACH		
0292	SPV.0060 Special 28. BOLT DOWN ALUMINUM POLE 17' WITH TRANSFORMER BASE	3.000 EACH		
0294	SPV.0060 Special 29. BOLT DOWN ALUMINUM POLE 22' WITH TRANSFORMER BASE	14.000 EACH		
0296	SPV.0060 Special 30. BOLT DOWN ALUMINUM POLE 29' WITH TRANSFORMER BASE	31.000 EACH		
0298	SPV.0060 Special 31. LIGHTING CONTROL CABINET 120/240 SPECIAL	1.000 EACH		
0300	SPV.0060 Special 32. CONCRETE BASE TYPE 7 SPECIAL	40.000 EACH		



Proposal Schedule of Items

Proposal ID: 20180612010 Project(s): 2060-10-70

Federal ID(s): WISC 2018319

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0302	SPV.0060 Special 33. LUMINAIRE ARMS STEEL 8 FT	2.000 EACH	_____	_____
0304	SPV.0060 Special 34. CONCRETE CONTROL CABINET BASE TYPE L SPECIAL	1.000 EACH	_____	_____
0306	SPV.0060 Special 35. ADJUSTING TES MANHOLE COVERS	15.000 EACH	_____	_____
0308	SPV.0060 Special 36. 4' DIAMETER MANHOLE TYPE TES	10.000 EACH	_____	_____
0310	SPV.0060 Special 37. INSTALLING CONDUIT INTO EXISTING MANHOLE	2.000 EACH	_____	_____
0312	SPV.0060 Special 38. TEMPORARY BUS LOADING ZONE	2.000 EACH	_____	_____
0314	SPV.0060 Special 39. Tiger Eye Sumac, #5, CG	8.000 EACH	_____	_____
0316	SPV.0060 Special 40. Miscanthus Panicum, #1, CG	8.000 EACH	_____	_____
0318	SPV.0060 Special 41. Rugosa Roses, #1, CG	20.000 EACH	_____	_____
0320	SPV.0060 Special 42. Diablo Ninebark, 4' HT, CG	10.000 EACH	_____	_____
0322	SPV.0060 Special 43. Perennial Black Eyed Susan, #1, CG	120.000 EACH	_____	_____
0324	SPV.0060 Special 44. Perennial Blue Wonder Catmint, #1, CG	212.000 EACH	_____	_____
0326	SPV.0060 Special 45. Perennial Pardon Me Daylilies, #1, CG	144.000 EACH	_____	_____
0328	SPV.0060 Special 46. Perennial Russian Sage, #1, CG	32.000 EACH	_____	_____



Proposal Schedule of Items

Proposal ID: 20180612010 Project(s): 2060-10-70

Federal ID(s): WISC 2018319

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0330	SPV.0060 Special 47. Perennial Stella Daylilies, #1, CG	72.000 EACH	_____	_____
0332	SPV.0060 Special 48. Joe Pye Weed, #1, CG	8.000 EACH	_____	_____
0334	SPV.0060 Special 49. Perennial Montrose White Catmint, #1, CG	392.000 EACH	_____	_____
0336	SPV.0060 Special 50. Perennial Pink Catmint, #1, CG	1,111.000 EACH	_____	_____
0338	SPV.0060 Special 51. Perennial Walkers Low Catmint, #1, CG	1,030.000 EACH	_____	_____
0340	SPV.0060 Special 52. Perennial Happy Returns Daylily, #1, CG	773.000 EACH	_____	_____
0342	SPV.0060 Special 53. Perennial Little Wine Cup Daylily, #1, CG	852.000 EACH	_____	_____
0344	SPV.0060 Special 54. Perennial Mini Stella Doro Daylily, #1, CG	1,844.000 EACH	_____	_____
0346	SPV.0060 Special 55. Perennial Moses Fire Daylily, #1, CG	1,972.000 EACH	_____	_____
0348	SPV.0060 Special 56. Perennial Purple Doro Daylily, #1, CG	1,290.000 EACH	_____	_____
0350	SPV.0060 Special 57. Perennial Rosey Returns Daylily, #1, CG	808.000 EACH	_____	_____
0352	SPV.0060 Special 58. Ornamental Grass Prairie Dropseed, #1, CG	1,540.000 EACH	_____	_____
0354	SPV.0090 Special 01. CONSTRUCTION STAKING CONCRETE SIDEWALK	7,690.000 LF	_____	_____



Proposal Schedule of Items

Proposal ID: 20180612010 Project(s): 2060-10-70

Federal ID(s): WISC 2018319

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0356	SPV.0090 Special 02. STORM SEWER PIPE CORRUGATED PVC 12 INCH	2,710.000 LF		
0358	SPV.0090 Special 03. CABLE TYPE 3#2/1#8 LTP	1,000.000 LF		
0360	SPV.0090 Special 04. CABLE TYPE 3#4/1#8 LTP	4,150.000 LF		
0362	SPV.0090 Special 05. CABLE TYPE 3#6/1#8 LTP	6,250.000 LF		
0364	SPV.0090 Special 06. CABLE TYPE 3#8/1#8 LTP	3,450.000 LF		
0366	SPV.0090 Special 07. 3 #10 UF UNDERGROUND CABLE WITH GROUND	1,000.000 LF		
0368	SPV.0090 Special 08. 8-DUCT CONDUIT, CEMENT ENCASED, 4-INCH RIGID NONMETALLIC CONDUIT DB-60	17.000 LF		
0370	SPV.0090 Special 09. 6-DUCT CONDUIT, CEMENT ENCASED, 4-INCH RIGID NONMETALLIC CONDUIT DB-60	210.000 LF		
0372	SPV.0090 Special 10. 4-DUCT CONDUIT, CEMENT ENCASED, 4-INCH RIGID NONMETALLIC CONDUIT DB-60	4,461.000 LF		
0374	SPV.0090 Special 11. 3-DUCT CONDUIT, CEMENT ENCASED, 4-INCH RIGID NONMETALLIC CONDUIT DB-60	18.000 LF		
0376	SPV.0090 Special 12. 2-DUCT CONDUIT, CEMENT ENCASED, 4-INCH RIGID NONMETALLIC CONDUIT DB-60	297.000 LF		
0378	SPV.0090 Special 13. Marking Line Epoxy 6-Inch	8,645.000 LF		
0380	SPV.0090 Special 14. Marking Stop Line Epoxy 24- Inch	425.000 LF		



Proposal Schedule of Items

Proposal ID: 20180612010 Project(s): 2060-10-70

Federal ID(s): WISC 2018319

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0382	SPV.0090 Special 15. Marking Crosswalk Epoxy 12-Inch	1,980.000 LF	_____	_____
0384	SPV.0090 Special 16. Conc C & G & B Cold Weather Covering Plastic 1 Layer	10,085.000 LF	_____	_____
0386	SPV.0090 Special 17. Conc C & G & Barrier Cold Weather Covering Plastic 2 Layer	10,085.000 LF	_____	_____
0388	SPV.0090 Special 18. Conc C & G & Barrier Cold Weather Cover Plastic/Hay/Plastic Or Blankets	10,085.000 LF	_____	_____
0390	SPV.0180 Special 01. JOINT SEALING	49,100.000 SY	_____	_____
0392	SPV.0180 Special 02. Conc Pavement Cold Weather Covering Plastic 1 Layer	24,550.000 SY	_____	_____
0394	SPV.0180 Special 03. Conc Pavement, Cold Weather Covering Plastic 2 Layers	24,550.000 SY	_____	_____
0396	SPV.0180 Special 04. Conc Pavement Cold Weather Covering Plastic/Hay/Plastic or Blankets	24,550.000 SY	_____	_____
0398	SPV.0195 Special 01. STORAGE LAYER	146.000 TON	_____	_____
0400	SPV.0195 Special 02. COBBLESTONES	18.000 TON	_____	_____
0402	SPV.0195 Special 03. MANAGEMENT OF SOLID WASTE	1,058.000 TON	_____	_____
Section: 0001			Total:	_____
			Total Bid:	_____